




| REFERENCE DRAWINGS | |
|-------------------------------|--------------|
| HARDWARE PACKAGE | 9957-900-001 |
| -SW SLEEVE / -MT TEMPLATE | 9925-214-001 |
| VALVES: | |
| -4 AIR-CONTROL (HOT & COLD) | 9905-000-003 |
| -3 AIR-CONTROL (SINGLE TEMP.) | 9905-001-003 |
| -MVC1 S/T TIME-TROL | 9905-201-003 |
| -MVC2 H&C TIME-TROL | 9905-200-003 |
| -EVS1 S/T MASTER-TROL | 9905-311-002 |
| -EVS2 H&C MASTER-TROL | 9905-310-002 |



MOUNTING DETAIL

| WASTE OUTLET | DIM "A" |
|--------------|---------|
| STANDARD | 10-1/4" |
| -PT OPTION | 6-3/4" |



REAR VIEW

INSTALLATION INSTRUCTIONS:

A-ROUGH-IN FOR FIXTURE WASTE OUTLET ①:

- 1-1/2" O.D. PLAIN END PROVIDED STANDARD & FOR -PT.
- 1-1/4" NPT FEMALE FOR -ELS/-PTS WASTE OPTIONS.
- 1-1/2" NPT FEMALE FOR -ELS/-PTS WITH -OS.

B-SEE REFERENCE DRAWING BOX FOR APPROPRIATE VALVE INSTALLATION DRAWINGS.

C-THREAD 1/2"-13 UNC STUDS ② INTO MOUNTING POINTS ③ AT REAR OF FIXTURE. STUDS ② MUST HAVE A MINIMUM 1/2" ENGAGEMENT.

D-PLACE LAVATORY ④ UP AGAINST THE WALL, SLIDING STUDS ② THROUGH SLEEVE OR WALL OPENINGS.


E-PLACE WASHERS ⑤ (OR PLATE) AND NUTS ⑥ ONTO STUDS ②. TIGHTEN TO 60 FT/LBS.

F-MAKE-UP LAVY WASTE CONNECTION - 1-1/2" O.D. PLAIN END (SUITABLE FOR A COMPRESSION CONNECTION).



ACORN ENGINEERING COMPANY
 P.O. BOX 3527 INDUSTRY, CA. 91744
 (626) 336-4561 FAX (626) 961-2200

| TITLE | | |
|---------------------------------------|-----------------|---------------------|
| 15" COMPACT LAVATORY CAT #1659 | | |
| MANUFACTURE DATE | DATE ISSUED | DRAWING NUMBER |
| APRIL 30, 1998 | 3/30/98 | 9925-155-002 |
| TO PRESENT | DATE REVISED | |
| | 03/12/02 | |



| REFERENCE DRAWINGS | |
|-------------------------|--------------|
| ASSEMBLIES | NUMBER |
| VALVE BODY | 9955-005-003 |
| CHECKSTOP | 9956-040-003 |
| FIXTURE TRIM | 9957-050-001 |
| -PBH/BPH TRIM | 9957-060-001 |
| AIR-CONTROL SERVOMOTORS | |
| METERING | 9955-000-003 |
| NON-METERING | 9955-001-003 |

NOTE:
THIS VALVE
SHOWN w/ (-MH)
METERING, HOT
SIDE ONLY



INSTALLATION INSTRUCTIONS:

- A- PRIOR TO INSTALLATION OF THE FIXTURE, MOUNT PUSHBUTTONS ① AND BUBBLER ② TO THE BACKSPLASH.
- B- INSTALL THE PLUMBING FIXTURE TO THE WALL INCLUDING UPPER SUPPORT PLATE ③.
- C- MOUNT THE AIR-CONTROL VALVE ASSEMBLY ④. LOCATE AS REQUIRED. MAXIMUM ALLOWABLE DISTANCE BETWEEN PUSHBUTTON ① AND AIR-CONTROL SERVOMOTOR ⑤ IS 10 FEET. WALL ANCHORING HARDWARE ARE BY OTHERS.
- D- CONNECT 1/8" O.D. POLYETHYLENE AIR LINES ⑥ TO PUSHBUTTONS ① AND SERVOMOTOR ⑤. HAND TIGHTEN USING FERRULE NUTS PROVIDED. SEE DETAIL A. NOTE: WHEN METERING VALVES ARE SPECIFIED, AIR LINES CONNECT DIRECTLY TO VALVE TIMER ⑦.
- E- CONNECT 1/4" O.D. POLYETHYLENE WATER LINE ⑧ TO BUBBLER ② AND COMPRESSION NUT ⑨. HAND TIGHTEN USING FERRULE NUTS PROVIDED.

NOTE:
MAXIMUM RECOMMENDED WORKING WATER PRESSURE IS 100 PSI; TEMPERATURE IS 130° F; OUTLET TEMPERATURE IS RECOMMENDED AT A MAXIMUM OF 105° F.
WARNING:
PRIOR TO MAKING INSTALLATION, SUPPLY LINES MUST BE FLUSHED OF ALL FOREIGN MATERIAL SUCH AS PIPE DOPE, CHIPS, SOLDER, ETC. VALVE MUST BE DRAINED PRIOR TO BEING SUBJECTED TO FREEZING TEMPERATURES. MAXIMUM RECOMMENDED OUTLET WATER TEMPERATURE IS 105° F.

- F- AFTER THOROUGHLY FLUSHING THE SUPPLY LINES, MAKE-UP 1/2" NPS FEMALE SUPPLY CONNECTIONS. NOTE: SUPPLY INLET CONNECTION WILL ACCOMODATE 1/2" NPT MALE ADAPTER. THREAD FLEX CONNECTOR HOSE ⑩ TO CHECKSTOPS ⑪ AND TO SUPPLY STUB OUTS.
- G- SEE APPROPRIATE SERVOMOTOR REFERENCE DRAWING FOR DETAILS AND TIMING INSRUCTIONS.

| | | |
|---|---|--|
| ACORN ENGINEERING COMPANY P.O. BOX 3527 INDUSTRY, CA. 91744 (626) 336-4561 FAX (626) 961-2200 | TITLE (04-SERIES) HOT & COLD AIR-CONTROL VALVE ASSEMBLY - NEW STYLE | |
| | MANUFACTURE DATE SEPT 1995 TO PRESENT | DATE ISSUED 11/1/95 DATE REVISED 07/15/10 |



WALL SLEEVE (-SW) BOTH VIEWS ARE FROM CELL SIDE METAL TEMPLATE (-MT)

RIGHT HAND FIXTURE ROUGH-INS SHOWN, LEFT HAND FIXTURE OPPOSITE



SHADED AREAS ARE REQUIRED WALL OPENINGS

WALL SLEEVE

SLEEVES ARE INSTALLED IN FORMS (USING NAIL HOLES ③ PROVIDED) OR GROUTED INTO BLOCK WALLS, BECOMING A PERMANENT PART OF WALL.

- A. INSTALL SLEEVE WITH FLANGE ④ ON CHASE SIDE OF WALL.
- B. LOCATE TOP AND BOTTOM NOTCHES AT VERTICAL CENTERLINE ② OF PLUMBING FIXTURE.
- C. LOCATE SIDE NOTCHES ① AT DIMENSION SHOWN, MEASURED FROM THE FINISHED FLOOR ON CELL (FIXTURE) SIDE.


NOTES:

- 1. FOR POURED WALL CONSTRUCTION, TEMPORARY BRACING SHOULD BE INSTALLED WITHIN SLEEVE OPENING TO PREVENT DEFORMATION TO SLEEVE WHICH MAY OCCUR DURING POUR. DO NOT POUR CONCRETE DIRECTLY ON TOP OF WALL SLEEVE.
- 2. WHEN SLEEVES ARE NOT AVAILABLE BLOCKOUT FOR SLEEVE OPENING IN WALL PER DIMENSIONS SHOWN ⑤.

METAL TEMPLATES (-MT)

TEMPLATES ARE USED TO LAYOUT REQUIRED WALL OPENINGS FOR SUBSEQUENT FLAME CUTTING OR CORE DRILLING.

- A. STRIKE A HORIZONTAL CHALKLINE ① ON THE WALL AT DIMENSION SHOWN, MEASURED FROM THE FINISHED FLOOR ON CELL (FIXTURE) SIDE. THIS WILL LOCATE CENTERLINE FOR HORIZONTAL NOTCHES ON TEMPLATE.
- B. STRIKE A VERTICAL CHALKLINE ② ON THE WALL TO INDICATE CENTERLINE OF FIXTURE. THIS WILL LOCATE CENTERLINE FOR VERTICAL NOTCHES ON TEMPLATE.
- C. PLACE TEMPLATE AGAINST WALL. LOCATE NOTCHES ALONG CHALKLINES. MARK WALL FOR REQUIRED OPENING.



WALL SLEEVE (-SW)




ACORN ENGINEERING COMPANY
P.O. BOX 3527 Industry, CA 91744
15125 Proctor Ave Industry, CA 91746
(626) 336-4561 FAX (626) 961-2200

| | | |
|---|--------------------------------|---------------------------------------|
| TITLE -SW WALL SLEEVE AND -MT METAL TEMPLATE - CAT. #1659 | | |
| MANUFACTURE DATE AUG 1975 TO PRESENT | DATE ISSUED 3-1-90 | DRAWING NUMBER 9925-214-001 |
| | DATE REVISED 5/17/16 | |



| DIMENSION "A" | |
|---------------|----------------|
| UP TO 8" WALL | 8" TO 12" WALL |
| 15-1/8" | 19-1/8" |



INSTALLATION INSTRUCTIONS:

A- AFTER INSTALLING ACORN UNIT ON FINISHED WALL, SLIP COMPRESSION NUT ① OVER 1-1/2" O.D. PLAIN END WASTE ②. USING COMPRESSION GASKET ③, AND NUT ① MAKE-UP COMPRESSION CONNECTION WITH SLIP JOINT ELBOW ④.

B- REMOVABLE TUBULAR P-TRAP ⑤ CONNECTS TO SLIP JOINT ELBOW ④ AND PLAIN END ELBOW ⑥ WITH COMPRESSION CONNECTIONS AS SHOWN.

NOTE: TUBULAR P-TRAP IS REMOVABLE IN ORDER TO ALLOW FOR WASTE CLEANOUT.

| | | |
|---|--|--|
| <p>ACORN ENGINEERING COMPANY P.O. BOX 3527 INDUSTRY, CA. 91744 (626) 336-4561 FAX (626) 961-2200</p> | <p>TITLE LAVATORY THRU-WALL WASTE CONNECTION w/ P-TRAP & CLEANOUT CAT. # -LW1</p> | |
| | <p>MANUFACTURE DATE APRIL 30, 1998 TO PRESENT</p> | <p>DATE ISSUED 3/19/98</p> <p>DATE REVISED 4/23/98</p> |